



## BID ADDENDUM NO. 2

CHILLER UPGRADES  
AT  
MIDWAY ELEMENTARY SCHOOL  
DINWIDDIE ELEMENTARY SCHOOL  
DINWIDDIE MIDDLE SCHOOL  
DINWIDDIE COUNTY PUBLIC SCHOOLS  
IFB # 23 – 012423 – 1R  
RRMM Project # 21215 - 02

May 2, 2023

This Addendum forms a part of the Construction Documents and modifies the bid documents dated April 4, 2023.

The information in this Addendum supersedes any contradictory information or omission set forth in the Contract Documents.

Where any component of the Contract Documents is modified or deleted by this Addendum, the unaltered components of that Section, Article, or Drawing shall remain in effect.

Acknowledge receipt of this Addendum by inserting its number and date in the Proposal Form. Failure to do so may subject Bidder to disqualification.

Bid Addendum No. 2 consists of this two (2) page Bid Addendum.

### CLARIFICATIONS

1.1 **Pre-Bid Questions & Responses.** See below questions with associated response to each question in *ITALIC* text.

**QUESTION #1:** According to feedback from electricians that reached out to the GE representative, panels and breakers are 19 weeks out. Can existing electrical circuitry be used to power new equipment until those special order components become available?

*RESPONSE: For Midway ES and Dinwiddie ES, new chillers can be powered from existing panels and breakers until new panels and breakers are available onsite. For Dinwiddie MS, the existing*

*breaker in the panel can be left at 500A, since we are providing a 450A fuse in the disconnect for Circuit 1 at each chiller.*

END OF BID ADDENDUM NO. 2